

ITEM	EXTENSION	DESCRIPTION	TOTAL	UNIT	UNIT PRICE	TOTAL AMOUNT	
		ROADWAY					
201	11000	CLEARING AND GRUBBING	LS			\$5,000.00	
202	23000	PAVEMENT REMOVED	522	SY	\$18.89	\$9,860.58	
202	30000	WALK REMOVED	1,067	SF	\$6.18	\$6,594.06	
202	32000	CURB REMOVED	215	FT	\$9.93	\$2,134.95	
202	35100	PIPE REMOVED, 24" DIAMETER AND UNDER	41	FT	\$19.87	\$814.67	\$24,404.26
		EROSION CONTROL					
601	32210	ROCK CHANNEL PROTECTION, TYPE C WITH AGGREGATE FILTER	218	CY	\$140.00	\$30,520.00	
832	30000	EROSION CONTROL	14,000	EACH	\$1.00	\$14,000.00	\$44,520.00
		DRAINAGE					
611	99920	DRAINAGE STRUCTURE, MISC.: TEMPORARY STORM OUTLET	1	LS	\$500.00	\$500.00	
613	41301	LOW STRENGTH MORTAR BACKFILL (TYPE 2), AS PER PLAN	401	CY	\$129.56	\$51,953.56	\$52,453.56
		STRUCTURE OVER 20 FOOT SPAN (ALL-CR176-4.92)					
202	11003	STRUCTURE REMOVED, OVER 20 FOOT SPAN, AS PER PLAN	LS			\$100,000.00	
202	23500	WEARING COURSE REMOVED	507	SY	\$12.77	\$6,474.39	
503	11100	COFFERDAMS AND EXCAVATION BRACING	LS			\$20,000.00	
503	21301	UNCLASSIFIED EXCAVATION, AS PER PLAN	LS			\$20,000.00	
503	31100	ROCK EXCAVATION	104	CY	\$108.55	\$11,289.20	
509	10000	EPOXY COATED STEEL REINFORCEMENT	46,917	LB	\$1.36	\$63,807.12	
511	31611	CLASS QC2 CONCRETE, SUPERSTRUCTURE, AS PER PLAN	140	CY	\$1,370.49	\$191,868.60	
511	44110	CLASS QC1 CONCRETE, ABUTMENT NOT INCLUDING FOOTING	164	CY	\$1,258.73	\$206,431.72	
511	46510	CLASS QC1 CONCRETE, FOOTING	106	CY	\$728.39	\$77,209.34	
512	10050	SEALING OF CONCRETE SURFACES (NON-EPOXY)	464	SY	\$19.63	\$9,108.32	
512	75500	SEALING: STAINING AND SEALING OF CONCRETE SURFACES	159	SY	\$100.00	\$15,900.00	
515	12091	PRESTRESSED CONCRETE COMPOSITE BOX BEAM BRIDGE MEMBERS, LEVEL 1, CB33-48, AS PER PLAN (81'-0 3/4")	11	EACH	\$33,750.00	\$371,250.00	
516	13900	2" PREFORMED EXPANSION JOINT FILLER	41	SF	\$12.37	\$507.17	
516	14020	SEMI-INTEGRAL ABUTMENT EXPANSION JOINT SEAL	115	FT	\$32.27	\$3,711.05	
516	31011	2" DEEP JOINT SEALER, AS PER PLAN	60	FT	\$16.63	\$997.80	
516	41100	1/8" PREFORMED BEARING PAD, TYPE CDP	22	EACH	\$41.56	\$914.32	
516	43201	ELASTOMERIC BEARING WITH INTERNAL LAMINATES ONLY (NEOPRENE), AS PER PLAN (2"x9"x10")	44	EACH	\$220.00	\$9,680.00	
517	75121	RAILING (CONCRETE PARAPET WITH TWIN STEEL TUBE RAILING), AS PER PLAN	257	FT	\$400.00	\$102,800.00	
518	21230	POROUS BACKFILL WITH GEOTEXTILE FABRIC	LS			\$10,000.00	
518	40000	6" PERFORATED CORRUGATED PLASTIC PIPE	146	FT	\$10.40	\$1,518.40	
518	40010	6" NON-PERFORATED CORRUGATED PLASTIC PIPE, INCLUDING SPECIALS	7	FT	\$20.00	\$140.00	
530	00200	STRUCTURES, MISC.: MOUNTED PLAQUE DISPLAY	LS			\$20,000.00	
530	13000	FORM LINER (DECORATIVE STONE FACING)	732	SF	\$22.19	\$16,243.08	
625	33000	STRUCTURE GROUNDING SYSTEM	1	EACH	\$4,843.33	\$4,843.33	\$1,264,693.84
		MAINTENANCE OF TRAFFIC					
616	10000	WATER	1	MGAL	\$26.27	\$26.27	\$26.27
		INCIDENTALS					
614	11000	MAINTAINING TRAFFIC	LS			\$8,000.00	
623	10000	CONSTRUCTION LAYOUT STAKES AND SURVEYING	LS			\$20,000.00	
624	10000	MOBILIZATION	LS			\$50,000.00	\$78,000.00

Grand Total = \$1,464,097.93